BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work: Resurve Fund to Emergency Works like water supply, Desilting of drains, shoulders drains, maintenance of Culvets, drains etc, at Dasarahalli Sarrounding area Ward No 06 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	45.36	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	5.83	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
3	19.44	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm	5811.98	Rupees Five Thousand Eight Hundred Eleven and Ninety Eight Paise Only
4	4.86	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5627.54	Rupees Five Thousand Six Hundred Twenty Seven and Fifty Four Paise Only
5	32.40	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
6	32.40	Providing precast slab of 250mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
7	60	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XLVIII / I. 23) PWD SR 2018-19	Day	5695.00	Rupees Five Thousand Six Hundred Ninety Five Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	100	1024 - Hire Charges of Tractor 50 HP including Operator and Fuel (P. XLVIII/I. 20) PWD SR 2018-19	Day	2129.00	Rupees Two Thousand One Hundred Twenty Nine Only
9	750	Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-19 Page No. LVI/SL NO. 5)	Nos	446.20	Rupees Four Hundred Forty Six and Twenty Paise Only
10	36.00	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
11	45.36	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	60.42	Rupees Sixty and Forty Two Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate of price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2 Unit rates and prices shall be quoted by the tender in indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITBClause 19.1(b)

"No. 2 CORRECTION NIL"
"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.